


Netto-Raumflächen nach DIN 277

Projekt: 002 23-01 Zur Kleinbahn 2, Troisdorf
Ersteller: slohn
Datum / Zeit: 27.04.2023 / 10:57
Hinweis:

Geschoss	Bezeichnung Funktion	Bereich	Nr	Abmessungen	NUF [m ²]	TF [m ²]	VF [m ²]	LGF [m ²]
01 EG								
	Aufzug	R	1	1.750*1.470	2,573			
				Summe	2,573			
	Kühlräume	R	1	10.760*3.380	36,369			
				Summe	36,369			
	Meister	R	1	2.710*2.610	7,073			
				Summe	7,073			
	Technik	R	1	3.330*1.410	4,695			
				Summe	4,695			
	Treppe	R	1	2.120*1.430	3,032			
				Summe	3,032			
	Verkaufsfläche	R	1	612.791	612,791			
			2	-(0.600*0.410)	-0,246			
			3	-(0.600*0.400)	-0,240			
			4	-(0.590*0.350)	-0,207			
			5	-(0.350*0.350)	-0,123			
			6	-(0.350*0.350)	-0,123			
			7	-(0.350*0.340)	-0,119			
				Summe	611,733			
	VK Leiter	R	1	1.950*0.500	0,975			
			2	2.765*1.532	4,236			
			3	0.5* (2.765+2.037)*0.728	1,748			
			4	1.430*1.130	1,616			
				Summe	8,575			
	Vorbereitung	R	1	4.650*0.245	1,139			
			2	4.900*3.330	16,317			
				Summe	17,456			
	Warenannahme	R	1	5.400*3.380	18,252			
			2	1.600*0.150	0,240			
			3	1.940*1.460	2,832			
			4	2.750*1.290	3,548			
			5	1.610*1.430	2,302			
				Summe	27,174			
Summe 01 EG					718,680			

02 OG

	Archiv	R	1	3.115*3.100	9,657			
				Summe	9,657			
	Aufzug	R	1	1.750*1.470	2,573			
				Summe	2,573			
	Aufzugmr.	R	1	1.950*1.930	3,764			
				Summe	3,764			



Netto-Raumflächen nach DIN 277

Projekt: 002 23-01 Zur Kleinbahn 2, Troisdorf
 Ersteller: slohn
 Datum / Zeit: 27.04.2023 / 10:57
 Hinweis:

Geschoss	Bezeichnung Funktion	Bereich	Nr	Abmessungen	NUF [m ²]	TF [m ²]	VF [m ²]	LGF [m ²]
	Flur	R	1	10.240*1.500	15,360			
			2	2.120*1.135	2,406			
			3	3.270*3.250	10,628			
				Summe	28,394			
	Lager	R	1	17.450*2.150	37,518			
			2	21.770*7.580	165,017			
				Summe	202,535			
	Lüftung Klima 1	R	1	7.750*4.780	37,045			
				Summe	37,045			
	Lüftung Klima 2	R	1	6.290*4.780	30,066			
				Summe	30,066			
	Lüftung Klima 3	R	1	3.270*3.030	9,908			
				Summe	9,908			
	Teeküche	R	1	4.810*4.000	19,240			
				Summe	19,240			
	Umkleide	R	1	3.130*3.100	9,703			
				Summe	9,703			
	WC D	R	1	2.740*1.820	4,987			
			2	2.740*1.130	3,096			
				Summe	8,083			
	WC H	R	1	2.770*1.820	5,041			
			2	2.770*1.130	3,130			
				Summe	8,171			
Summe 02 OG					369,139			
Gesamtsumme					1087,819			

Übersicht Geschosse / Umschließungsart		R [m ²]	Gesamt
01 EG	NUF 1	718,680	718,680
02 OG	NUF 1	369,139	369,139
Gesamt		1087,819	1087,819